

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52

**SECTION 06 10 00
ROUGH CARPENTRY**

SCOPE

The work under this section includes all labor, material, equipment and related services necessary to install rough framing and blocking.

PART 1 - GENERAL

- Scope
- References
- Quality Assurance

PART 2 - PRODUCTS

- Materials

PART 3 - EXECUTION

- Installation

PART 1 - GENERAL

In the event that the Contractor wishes to make improvements in materials and/or techniques, or is required to make improvements by his material manufacturer in order to obtain guarantees, he shall make written request stating in full the nature of the proposed changes and stating that the changes, if approved, will be accomplished at no additional cost to contract.

REFERENCES

- All applicable provisions of Division 1 govern work under this Section.
- ALSC PS 20 - American Softwood Lumber Standard.
- APA - American Plywood Association.

QUALITY ASSURANCE

All lumber used on this project shall be graded by an agency certified by ALSC.

PART 2 – PRODUCTS

MATERIALS

Softwood Lumber: ALSC PS20, grade No. 2 or better; 19 percent maximum moisture content, size as detailed or required.

Fasteners: Sizes and lengths to suit conditions.

Wood to Wood: Double hot-dipped, galvanized nails.

Wood to Concrete or Masonry: Zinc alloy expansion shield or case hardened steel lag.

Wood to Metal: #10 stainless steel sheet metal screws flat heads.

Other products, not specifically described, but required for a complete and proper installation of the work in this section, shall be selected by the Contractor subject to approval by the DFD Project Manager

PART 3 - EXECUTION

INSTALLATION

Refer to the detail drawings included with these specifications. Install material as follows for new or corrective work, where required.

1 Shim, install provide and securely fasten all wood nailers and blocking as detailed or required. Use longest
2 lengths practical to minimize joints; stagger all joints a minimum of 8". Unless noted otherwise all
3 materials shall be fastened using two rows of fasteners @ 24" O.C. staggered.

4
5
6

END OF SECTION